



PROPOSAL - CONTRACT

CMI Management
Mr. Steve Miller
5285 Shawnee Rd.
Alexandria, VA. 22312

Sep 2, 2019

RE:

CSS19946 New Windsor USAR Doorway overhang soffits at three entry points to the training building need to be replaced due to high wind and water damage. The areas are the training building rear entry, kitchen entry and the main entry point. The main entry point has a leak in the roof causing continuing water damage. Urgent

- Remove existing overhang soffit panels at all three entry points.		
- Install 2x6 structural rough framing and furring strips.		
- Install perimeter trim cap		
- Install new soffit panels to match existing.		
- Remove and re-install existing light fixtures		
- Repair flashing leak on front roof		
-	(62)pcs. vinyl soffit. 9.99.	619.38
	(15) pcs Channel cap 4.88.	73.20
	(20) 2x6x16ft. Home Depot 12.52	252.40
	Misc hardware & calk.	50.00

		994.98
	Tax 7%.	69.65

		1064.63
	20%	212.93.

		1277.56
	Labor 130 hrs @120.00	15600.00

		16877.56

701 Randall Rd Ballston Spa, NY 12020 TEL 518-441-6003 FAX 518-399-5440

Email rdpostulka@verizon.net

INDUSTRIAL

COMMERCIAL

INSTITUTIONAL



INDUSTRIAL

COMMERCIAL

INSTITUTIONAL